

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21864-00-00  
Spot: SWSW Sec/Twnshp/Rge: 14-30S-7W  
660 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: DUNKELBERGER Well #: 5  
County: KINGMAN Total Vertical Depth: 4250 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS, INC. OF KANSAS  
Address: PO BOX 8647  
WICHITA, KS 67208

PROD Size: 4.5 feet: 4250 125 SX CMT  
SURF Size: 8.625 feet: 281 215 SX CMT

*A13813*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/08/2004 3:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTRYE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Perfs 4114'-4124'  
Plugging Sand to 4050' & 4 sxs  
Method: 1200' & 35 sxs  
700' & 35 sxs  
330' & circ to surf

RECEIVED  
KCC DISTRICT #2  
NOV 15 2004  
WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 11/08/2004 3:00 PM KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

The perforations were covered with sand to 4041' and capped with 4 sacks of cement. Recovered casing from 3520' and pulled to 1200'. Pulled casing to 700' and spotted 35 sacks of cement. Pulled casing to 330' and circulated cement to surface.

60/40 posmix with 4% gel  
Allied Cement #20286

**Perfs:**

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4114 | 4124 |      |          |


RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 16 2004  
CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

INVOICED

DATE 12-17-04

INV. NO. 2005060944