

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22941-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 29-25S-11W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: THOMAS Well #: 1
County: STAFFORD Total Vertical Depth: 4175 feet

Operator License No.: 30128
Op Name: WHITE, KENNETH S.
Address: 2400 N. WOODLAWN, SUITE 115
WICHITA, KS 67220

PROD Size: 5.5 feet: 4148 WITH 175 SX CMT
SURF Size: 10.75 feet: 258 WITH 175 SX CMT

\$135⁶⁹

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/07/2004 10:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: FILL WITH SAND TO 3800' & DUMP 5 SX CMT. PLUG AT 650' WITH 50 SX CMT. PLUG AT 275' WITH 75 SX CMT. PLUG AT 40' WITH 25 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 12/07/2004 12:05 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 3800' & 5 SX CMT. PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 650' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 275' WITH 75 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4111	4114		
3943	3956		

RECEIVED
DEC 16 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2340' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE

12-17-04

INV. NO.

2005060947

Form CP-2/3