

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-049-21827-00-00
Spot: NENWNW Sec/Twnshp/Rge: 2-30S-9E
4950 feet from S Section Line, 4290 feet from E Section Line
Lease Name: PERKINS Well #: 1
County: ELK Total Vertical Depth: 2475 feet

Operator License No.: 4448
Op Name: PERKINS OIL ENTERPRISES, INC.
Address: PO BOX 707
HOWARD, KS 67349

PROD Size: 5.5 feet: 2475
SURF Size: 8.625 feet: 100

8044

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/21/2004 8:00 AM
Plug Co. License No.: 5684 Plug Co. Name: SAGE, LARRY GEORGE
Proposal Rcvd. from: JIM PERKINS Company: PERKINS OIL CO. Phone: (620) 374-2133

Proposed Plugging Method: TO PUMP CEMENT FOR BOTTOM, MIDDLE, & TOP PLUGS.

Plugging Proposal Received By: RON ROWE Witness Type: PARTIAL
Date/Time Plugging Completed: 10/25/2004 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

Perfs:

DUMP-BAILED 7 SACKS CEMENT @ 2425' FOR BOTTOM PLUG. SHOT-OFF 5.5 CASING @ 1540' & PULLED OUT. RAN 2" WORK STRING TO 1340' & PUMPED 17 SACKS CEMENT FOR MIDDLE PLUG. PULLED 2" TO 550' & PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 2" & TOPPED-OFF WELL. USED TOTAL OF 210 SACKS CEMENT.

RECEIVED
KCC DISTRICT #3

DEC 13 2004 RR

CHANUTE, KS

RECEIVED
DEC 17 2004
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)

INVOICED

DATE 12-17-04

INV. NO. 2005060950