

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-111-20338-00-00
Spot: NWSESW Sec/Twnshp/Rge: 34-21S-10E
1004 feet from S Section Line, 3834 feet from E Section Line
Lease Name: PIXLEE C Well #: 29
County: LYON Total Vertical Depth: 2250 feet

Operator License No.: 5697
Op Name: JACKSON BROS., L.L.C.
Address: 116 EAST THIRD ST.
EUREKA, KS 67045

PROD Size: 4.5 feet: 2233
SURF Size: 8.625 feet: 107

73' 3

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/26/2004 8:00 AM

Plug Co. License No.: 5684 Plug Co. Name: SAGE, LARRY GEORGE

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' CEMENT PLUG @ 2200' 50' CEMENT PLUG @ 1000' 250' CEMENT PLUG TO SURFACE.

Plugging Proposal Received By: MICHAEL HEFFERN

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 12/02/2004 5:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

BUILT ROCK BRIDGE @ 2142' INSIDE CASING, MIXED&DUMPED 8 SXS CEMENT WITH DUMP BALER @ 2142' TO 2067', SHOT CASING @ 880', PUMPED 25 SXS CEMENT THRU TUBING @ 850', PULLED TUBING OUT, PULLED CASING OUT, RAN TUBING BACK IN TO 250' PUMPED 75 SXS CEMENT TO SURFACE. CEMENT FELL BACK 70' PUMPED 15 SXS CEMENT TO SURFACE.

RECEIVED
KCC DISTRICT #3

DEC 13 2004

CHANUTE, KS

MH

RECEIVED
DEC 17 2004
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern
(TECHNICIAN)

INVOICED

DATE 12-17-04

INV. NO. 20050160948