

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20959-00-00
Spot: W2SENE Sec/Twnshp/Rge: 3-17S-10W
3300 feet from S Section Line, 990 feet from E Section Line
Lease Name: SCHROEDER Well #: 1-B
County: ELLSWORTH Total Vertical Depth: 3325 feet

Operator License No.: 30458
Op Name: RJM COMPANY
Address: PO BOX 256
CLAFLIN, KS 67525

PROD Size: 5.5 feet: 3315 150 SX CMT
SURF Size: 8.625 feet: 326 165 SX CMT

#108⁰⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/10/2004 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: EDWARD S NEMNICH Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Sand to 3250 w/ 5 sxs; 1300' w/ 35 sxs; 950' w/ 35 sxs; and 375' - 0'.

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 16 2004
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received By: _____
Date/Time Plugging Completed: 12/10/2004 4:00 PM

WitnessType: COMPLETE (100%)
KCC Agent: JACK LUTHI

RECEIVED
KCC DISTRICT #2
DEC 13 2004
WICHITA, KS

Actual Plugging Report:

Sanded bottom to 3250' and 5 sacks of common cement. Cut 5-1/2" casing at 1350' and pumped 35 sacks of cement. Pulled to 950' and pumped 35 sacks of cement. Pulled to 375' and circulated cement to surface.

Copeland Cement

60/40 posmix with 4% gel.

Perfs: _____

Remarks:

Plugged through: CSG

District: 02

Signed

Jack Luthi

(TECHNICIAN)

INVOICED

DATE

12-17-04

WV. NO.

2005060946