

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-04298-00-00  
Spot: SESESW Sec/Twnshp/Rge: 4-21S-6W  
330 feet from S Section Line, 2310 feet from W Section Line  
Lease Name: FREEMAN Well #: 5  
County: RICE Total Vertical Depth: 3467 feet

Operator License No.: 6627  
Op Name: PROSPECT OIL & GAS CORP  
Address: PO BOX 837  
RUSSELL, KS 67665

PROD Size: 5.5 feet: 3467 150 SX CMT  
SURF Size: 8.625 feet: 160 150 SX CMT

#112<sup>68</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/30/2004 1:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOE MACE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Sand to 3380'; 35 sxs @ 1100'; 35 sxs @ 600'; and 300' to 0'.  
Plugging Method:

RECEIVED  
KCC DISTRICT #2  
DEC 13 2004  
WICHITA, KS

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: PARTIAL  
Date/Time Plugging Completed: 11/30/2004 4:00 PM KCC Agent: JACK LUTHI

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 16 2004

Actual Plugging Report:

Sanded bottom to 3380' and 5 sacks of common cement. Cutting 5-1/2" casing at 2400'; it parted at 800'. Perforated pipe at 1100' and pumped 35 sacks of cement. Ran tubing to 1100', pulled to 600', and pumped 35 sacks of cement. Pulled to 300' and circulated cement to 0'.

Copeland

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3433	3438		

Remarks:

Plugged through: CSG

District: 02

Signed

Jack L Luthi  
(TECHNICIAN)

INVOICED  
DATE 12-17-04  
INV. NO. 2005060945