

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-175-21517-00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date spud 12/9/95.

Well Operator: Marlin Oil Corporation KCC License #: 9228
Address: P.O. Box 14630 (Owner / Company Name) City: Oklahoma City (Operator's)

State: Oklahoma Zip Code: 73113 Contact Phone: (405) 478-1900

Lease: GASKILL Well #: 5-5 Sec. 5 Twp. 31 S. R. 33 East West
- NW/4 - NW/4 - SE/4 Spot Location / QQQQ County: Seward

2292 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)
2325 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8-5/8" Set at: 1865' Cemented with: 900 Sacks
Production Casing Size: 5-1/2" Set at: 5649' Cemented with: 575 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perforations: 5338-42'; 5256-72'; 5030-34'; 4782-88'; 4609-12'; 4200-02'
CIBP set at 5230'

Elevation: 2932' / 2937' (G.L. / K.B.) T.D.: 5650' P.B.T.D.: 5230' Anhydrite Depth: 1710 to 1790'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Load hole with mud, set CIBP at 4170', cap plug with 1 sx cmt, spot 40 sx cmt plug at 1915-1815' and a 10 sx cmt plug at 33-3', cut off 8-5/8" and 5-1/2" csg 3' below ground level and weld on ID plate.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? A copy of the log tops is attached.

RECEIVED
NOV 24 2004
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Dick Lynn

Phone: (405) 818-8738

Address: PO Box 14630 City / State: Oklahoma City, OK 73113

Plugging Contractor: Sargent and Horton Plugging, INC. KCC License #: 31151

Address: Route 1, Box 49BA, Tyrone, OK 73951 Phone: (580) 854-6515

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 11/19/04 Authorized Operator / Agent: _____

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Marlin Oil Corporation
PO Box 14630
Oklahoma City, OK 73113-0630

December 10, 2004

Re: GASKILL #5-5
API 15-175-21517-00-01
NWNWSE 5-31S-33W, 2292 FSL 2325 FEL
SEWARD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely



David P. Williams
Production Supervisor