

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

API # 15-075-205²76-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 03/26/94

Well Operator: Chesapeake Operating, Inc. KCC License #: 32334
(Owner/Company Name) (Operator's)

Address: P. O. Box 18496 City: Oklahoma City, OK 73154-0496

State: OK Zip Code: 73154-0496 Contact Phone: (405) 848-8000

Lease: Osborne Well #: 2-31 Sec. 31 Twp. 23S S. R. 40 East West

SE NW NW Spot Location / QQQQ County: Hamilton

4030 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

4030 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8 Set at: 326' Cemented with: 185 Sacks

Production Casing Size: 4-1/2 Set at: 2487' Cemented with: 7-0 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2429'-2444'

Elevation: 3343' (G.L. / K.B.) T.D.: 2487' PBDT: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Tie onto 4-1/2" csg, pump 300# cotton seed hulls to plug perms; follow hulls w/135 sx cmt to surface, dig out braden head, pump 50 sx cmt into 4-1/2"x8-5/8" annulus if possible.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

**RECEIVED
NOV 24 2004
KCC WICHITA**

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Bud Neff Phone: (620) 277-0803

Address: 4532 W. Jones Avenue City / State: Garden City, KS 67846

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: _____
(Company Name) (Contractor's)

Address: P. O. Box 31, Russell, KS 67665 Phone: ()

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 11/19/04 Authorized Operator / Agent: Barbara J. Bale for Jim Reisch
Jim Reisch (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Chesapeake Operating, Inc.
PO Box 18496
6200 N Western Ave.
Oklahoma City, OK 73154-0496

December 10, 2004

Re: OSBORNE #2-31
API 15-075-20526-00-00
SENWNW 31-23S-40W, 4030 FSL 4030 FEL
HAMILTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely

David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888