

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

15-137-00100-00-00

WELL PLUGGING APPLICATION FORM

File One Copy

Lease Owner Benson-Montin Address Petroleum Building
(Applicant) Oklahoma City, Oklahoma.
Lease (Farm Name) Voss Well No. # 1
Well Location NE-NE-SW Sec 29 Twp. 5 Rge. 21 (E)-(W) W
County Norton Field Name (if any) Wildcat
Total Depth 3771 Ft. Oil Gas Dry Hole dry hole
Was well log filed with application? Yes . If not, explain:

Date and hour plugging is desired to begin

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desired.
(Use an additional sheet if necessary)

Name of the person on the lease in charge of well for owner

T.C. Strain Address Box 188, Hays, Kansas

Name of Plugging Contractor Strain Drilling Co.

Address Box 188, Hays, Kansas.

Invoice covering assessment for plugging this well should be sent to

Benson-Montin Address Petroleum Building,
Oklahoma City, Okla.

and payment will be guaranteed by applicant.

FILE 29 5 R 216
BOOK PAGE 13 LINE 38

T.C. Strain
T.C. Strain
Applicant or Acting Agent

Date May 3, 1952

RECEIVED
STATE CORPORATION COMMISSION
05-06-1952



STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

May 5, 1952

15-137-00100-00-00

Well No.	1
Lease	Voss
Description	NE 1/4 SW 29-5-210
County	Horton
File No.	13-38

Benson-Martin, Inc.
Petroleum Bldg.
Oklahoma City, Oklahoma

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Potty, Box 386, Hays, Kansas.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

BY: J. P. Roberts
J. P. ROBERTS

cc: DISTRICT PLUGGING SUPERVISOR

COMPANY: Brooks Hall & Strain Drilling Co.

NE-NE-SW Sec. 29, Twp. 5, Rge 21, Norton County, Kansas

ELEVATION: 2328 B. F.

NOTE: All meas. rotary bushings.

0 73 Clay & Sand
 73 90 Hole Sand
 90 110 Shale & Sand
 110 200 Sand
 200 490 Grey & Blue Shale
 490 550 Shale
 550 1020 Shale & Shells
 1020 1310 Sand & Shale
 1310 1595 Shale & Shells
 1595 1900 Shale & Shells & Redbed
 1900 1940 Shale & Redbed
 1940 1975 Anhydrite
 1975 2065 Shale & Shells
 2065 2265 Shale & Shells
 2265 2465 Shale & Line
 2465 2570 Shale & Shells
 2570 2715 Shale & Line
 2715 2840 Shale & Line
 2840 2880 Shale & Line
 2880 2990 Line & Shale
 2990 3095 Line & Shale
 3095 3170 Shale & Line
 3170 3265 Shale & Shells
 3265 3321 Shale
 3321 3380 Line & Shale
 3380 3460 Line & Shale
 3460 3505 Line
 3505 3530 Line
 3530 3585 Line
 3585 3612 Line

3612 3645 Line
 3645 3675 Line
 3675 3710 Line
 3710 3760 Line & Shale
 3760 3771 Reagan Sand
 3771 (Total Depth) B. S.

COMMENCED: 4-19-52
COMPLETED: 5-2-52

Casing Record:

8 5/8 Surface Casing set at 222' w/150 lbs cement by Globe Cementing Co.

B.S.T. by Johnston Testers

3552-3612 Toolopen 30 min. recovered 20' mud B.H.P. 1020#

3657-3710 Toolopen 30 Min. weak-blow recovered 17' mud and 1" of free oil B.H.P. 15 min. 525#

3760-3771 Toolopen 1 hour recovered 126' of oil spotted mud 450 salt water B.H.P. 15 min. 1065#

Schlumberger Log run to Total Depth.

TOPS:

GEOLOGIST A. D. Dodge.

Topoka	3318 (-987)	T. D. 3771 (-1440)	Lansing	3534 (-1293)
Heebner	3489 (-1156)		Bass K. C.	3719 (-1388)
Toronto	3516 (#1185)		Reagan	3771 (-1440)

STATE OF KANSAS) SS
COUNTY OF ELLIS)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Voss # 1, located NE-NE-SW, Sec. 29, Twp 5, Range 21, Norton County, Kansas.

CONTRACTOR Strain Drilling Company

PLUGGING
 FILE SEC 29 T. 5 R. 21 W
 BOOK PAGE 13 LINE 29

BY *J. O. Strain*
RECEIVED
 STATE CORPORATION COMMISSION
 MAY - 6 1952

Subscribed and sworn to before me this 3rd day of May, 1952

My commission expires March, 26, 1956

Wichita, Kansas
W. J. Schneider
 Notary Public.