

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: R.J.M. Oil Company
Address: P.O. Box 256
Phone: (620) 587-3910 Operator License #: 30458
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: December 8th, 2004 (Date)
by: Virgil Clothier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: N/A Bottom: N/A T.D. 3325'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-053-20,959-00-00
Lease Name: Schroeder "B"
Well Number: #1
Spot Location (QQQQ): C - W/2 - SE - NE
3300 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 3 Twp. 17 S. R. 10 East West
County: Ellsworth
Date Well Completed: 9/19/85
Plugging Commenced: 12/09/04
Plugging Completed: 12/10/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	326'	8-5/8"	326'	0'
	Production	0'	3315'	5-1/2"	3315'	1413.75'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


M.I.R.U. Ran bailer to bottom. Sand off 3250'-let sand fall. Spot 5 sx. M.I.R.U. casing jacks. Pulled casing out of slips. Broke head off. Worked and pulled stretch and trip in hole with casing knife. Tried to cut at 1700' & 1550'. Finally freed at 1400'. Pulled to 1300' - Copeland pumped 35 sx and 200# hulls. Pulled to 950'-pumped 50 sx; Pulled to 375'-pump has pressure; Pulled to 300'-pumped 80 sx and pulled rest of pipe. Cleaned up, rigged down and moved off.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc License #: 6901
Address: P.O. Box 231, Claflin, Kansas 67525

Name of Party Responsible for Plugging Fees: R.J.M. Oil Company
State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Edward S. Nemnich
(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED and SWORN TO before me this 14th day of December, 20 04

Karen J. Mitchell
Notary Public

My Commission Expires: 4/13/12

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
DEC 17 2004
KCC-WICHITA

Bw