

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market - Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-075-00114-0000

LEASE NAME HELTEMES N A

WELL NUMBER 3-25

2490' FSL Ft. from S Section Line

2490' FWL Ft. from E Section Line

SEC. 25 TWP. 26S RGE. 40W (E) or (W)

COUNTY HAMILTON

Date Well Completed 4/26/52

Plugging Commenced 12/02/04

Plugging Completed 12/09/04

RECEIVED

DEC 17 2004

KCC WICHITA

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # (72) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/25/04, 9/08/04 (date)

by DAVID WILLIAMS (KCC District Agent's Name)

is ACO-1 filed? YES If not, is well log attached?

Producing Formation CHASE Depth to Top 3356' KB Bottom 2568' T.D. 2568'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
CHASE	GAS	2418'	2568'	10 3/4"	460'	0
				7"	2442'	500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

12/2-9/04 P&A Operations witnessed by K Jehlick, KCC. POOH tbq. rods. subs. Cmtr mix & pmp 400# cshs w/20 bbl mud & 35 sx cmt plug 2418'-2243'. Load w/80 bbl mud. Cut 7" csg@ 717'. POOH 7" csg to 500', circ hole w/50 bbl mud & 75 sx cmt plug 500'-350' & 15 bbl mud. Load hole w/ 5 bbl mud to 40', pmp 20 sx cmt plug from 40' to 0'. Cut 10 3/4" csg 3' bgl, weld trash cover ID plate. RDMO.


Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.

LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God



(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039

SUBSCRIBED AND SWORN TO before me this 15th day of DECEMBER, 20 04

My Commission Expires: 5/21/2005

Angie G Hernandez
Notary Public

USE ONLY ONE SIDE OF EACH FORM

Form CP-4
Revised 05-88

Bm