

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Gore Oil Company  
Address: P.O. Box 2757, Wichita, KS 67201-2757  
Phone: (316) 263-3535 Operator License #: 5552  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 10-5-04 (Date)  
by: David P. Williams (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
LKC Depth to Top: 3377' Bottom: 3396' T.D. 3474'  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-137-20300-00-00  
Lease Name: Hockman  
Well Number: #4  
Spot Location (QQQQ): W/2 - SE - NE -  
1980 Feet from  North /  South Section Line  
990 Feet from  East /  West Section Line  
Sec. 12 Twp. 5 S. R. 22  East  West  
County: Norton  
Date Well Completed: 9-30-83  
Plugging Commenced: 10-14-04  
Plugging Completed: 10-14-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface	Oil	0'	207'	8 5/8"	207'	0'
Production	Oil	0'	3473'	4 1/2"	3473'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Run tubing to 1800'. Hooked up Swift and pumped 65 sx SMD cement w/200# hulls down tubing, circ to surface. Pulled tubing out and hooked to casing. Pumped 45 sx cement w/300# hulls. SIP 600 psi. Had welder cut off casing and weld collar in surface pipe. Hooked to surface and pumped 35 sx SMD cement. SIP 50 psi. Job complete.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382  
Address: P.O. Box 466, Ness City, KS 67560-0466  
Name of Party Responsible for Plugging Fees: Gore Oil Company  
State of Kansas County, Sedgwick, ss.  
Larry M. Jack

RECEIVED  
DEC 17 2004  
KCC WICHITA

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry M Jack  
(Address) Wichita, KS



SUBSCRIBED and SWORN TO before me this 30th day of November, 20 04  
Rebecca K. Crawford My Commission Expires: 3-20-07  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Handwritten initials*