

API NUMBER 15-067-20201-0000
LEASE NAME KIRMAYER Estate
WELL NUMBER 3-24
1920' FSL Ft. from S Section Line
1320' FWL Ft. from E Section Line
SEC. 24 TWP. 29S RGE. 37W (E) or (W)
COUNTY GRANT
Date Well Completed 8/23/72
Plugging Commenced 12/02/04
Plugging Completed 12/07/04

RECEIVED
DEC 17 2004

TYPE OR PRINT
NOTICE: Fill out completely
and return to GORS. Div.
office within 30 days

KCC WICHITA

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.
ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039
PHONE # (72) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS
(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/10/04, 11/15/04 (date)
by DAVID WILLIAMS (KCC District Agent's Name).
is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation COUNCIL GROVE Depth to Top 3071' KB Bottom 2972' T.D. 3000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
COUNCIL GROVE	GAS	2772'	2866'	10 3/4"	737'	0
				7"	2990'	750'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

12/2-7/04 P&A Operations witnessed by K Jehlick, KCC. POOH tbq, rods, subs. Cmtr mix & pmp 500# cshs w/12 bbl mud & 35 sx cmt plug 2773'-2600'. Load w/95 bbl mud. Cut 7" csg@ 1018'. POOH 7" csg to 750', circ hole w/50 bbl mud & 75 sx cmt plug 750'-600' & 30 bbl mud. Load hole w/ 5 bbl mud to 40', pmp 20 sx cmt plug from 40' to 0'. Cut 10 3/4" csg 3' bgl, weld trash cover ID plate. RDMO.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.

LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039



SUBSCRIBED AND SWORN TO before me this 15th day of DECEMBER, 20 04

My Commission Expires: 5/21/2005 Angie G. Hernandez Notary Public