


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Norton County, Sec. 29 Twp. 5S Rge. (E) 21(W)  
Location as "NE/CNW/SW" or footage from lines NE NE NE  
Lease Owner Jones, Shelburne & Farmer, Inc.  
Lease Name Damewood Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed 9-8 19 53  
Application for plugging filed 9-8 19 53  
Application for plugging approved 9-8 19 53  
Plugging commenced 9-8 19 53  
Plugging completed 9-8 19 53  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production Never produced 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Elden Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3682 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	160	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1. Filled hole with heavy mud
2. Pushed plug to 160'
3. Dumped 1/2 sack hulls on top of plug
4. Mixed 15 sacks cement and dumped on top of hulls
5. Filled hole to top
6. Pushed plug to 40'
7. Dumped in 1/2 sack hulls
8. Mixed 10 sacks cement and filled hole to top with same


(If additional description is necessary, use BACK of this sheet) 09-15-1953  
Name of Plugging Contractor D & M Drilling Company  
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
John O. Farmer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John O. Farmer  
Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of September, 19 53  
Donnie Berryhill  
Notary Public.

My commission expires April 23, 1956



15-137-00084-00-00-

DAMEWOOD #1

Rigged up Rotary Tools 8/30/53  
Tore down Rotary Tools 9/8/53

Ran 5 Jts. (160') 8 5/8" surface pipe  
set at 159'. Cemented with 100 sacks  
cement, 1 sack Cal. Cl.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface Sand	0'	159'
Shale	159	423
Gray shale, shells, redbed & sand	423	1156
Gray shale, shells, redbed & sand streaks	1156	1788
Shale	1788	1837
Anhydrite	1837	1880
Shale & sand	1880	2155
Lime & shale	2155	2280
Shale & shells	2280	2415
Lime	2415	2565
Lime & shale	2565	2740
Lime & shale streaks	2740	2828
Lime	2828	2923
Lime & shale	2923	3356
Lime	3356	3430
Lime, shale, & chert Streaks	3430	3432
Lime	3432	3504
Lime & chert	3504	3521
Lime, chert & shale	3521	3548
Lime, shale & chert streaks	3548	3574
Lime & shale	3574	3623
Lime, sandy shale	3623	3678
Lime & sand	3678	3682 TD

I, W. M. Barnett, do hereby certify that the foregoing log is true and correct, to the best of my knowledge and belief.

W. M. Barnett

Subscribed and sworn to before me this 11th day of September, 1953.

J. M. Swaney

My commission expires: July 29, 1957

**PLUGGING**  
FILE SEC 29 T 5 R 21W  
BOOK PAGE 128 LINE 34

DIVISION  
Geological Survey  
Kansas