

State of Kansas



15-137-00092-00-01

~~15-137-00229-00-00~~

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 10 1971

CONSERVATION DIVISION
Wichita, Kansas

6-10-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Virgil Shawn of Sage Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Shawn guarantees payment of the plugging fee.

Operator's full Name: Will P. Ash,

Complete Address: 230 Sutton Place, Wichita, Kansas.

Lease Name: Kemper Well No. 1

Location: SW-SW-NE Sec. 25 Twp. 5 Rge. (E)(W) 21

County: Norton Total Depth 3720' Oil Well

Gas Well Input Well SWD Well WASHDOWN D & A X Lost Hole

Mr. Shawn was instructed to plug the well as follows:

179'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 725'.

Circulate hole with heavy mud. Pull DP to 925' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent