



15-137-30068-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 7 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
10-7-74

Dear Sir:

Mr. Albert Unruh of SW Casing Pulling Co., Inc., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Leland R. Baird,

Complete Address: Logan, Kansas.

Lease Name: Baird Fee Well No. 1

Location: CS Line-NE-NE Sec. 23 Twp. 5 Rge. (E)(W) 21

County: Norton Total Depth 3611' Oil Well x

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Unruh was instructed to plug the well as follows:

207'--8 5/8" Surface casing, cement circulated with 150 Sx.  
3607'--4 1/2" Production casing cemented on bottom with 75 Sx. (Open hole completion). Top of Dakots section @ 775'.

Sand well back to 3590' and set 4 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

W. L. Nichols  
Conservation Division Agent