



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION

SEP 21 1973

CONSERVATION DIVISION Wichita, Kansas

9-21-73

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Kelso Casing Pulling has this date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center, Wichita, Kansas.

Lease Name: Kemper Well No. 1

Location: SE-SE-SW Sec. 23 Twp. 5 Rge. (E)(W) 21

County: Norton Total Depth 3644' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:

196'--8 5/8" Surface casing, cement circulated with 160 Sx. 3638'--5 1/2" Production casing cemented on bottom. Open hole completion.

Sand well back to 3600' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

H. L. Nichols Conservation Division Agent