



15-137-00310-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 15 1970
CONSERVATION DIVISION
Wichita, Kansas

9-15-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wilbur Crandall of Knight Casing Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Crandall guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Company,

Complete Address: Box #287, Great Bend, Kansas.

Lease Name: Kemper Well No. 5

Location: CSW-SW-NE Sec. 23 Twp. 5 Rge. (E)(W) 21

County: Norton Total Depth 3640' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Crandall was instructed to plug the well as follows:

399'--10 3/4" Surface casing, cement circulated.
3623'--7" OD Production Casing cemented on bottom with 150 Sx. 7" has been squeezed with 178 Sx. cement thru holes @ 2000' & 2500'.

Run wire line to establish bottom, pull 7" casing and squeeze well with 5 sacks hulls, 45 sacks gel and 175 Sx. cement, staged.

Very truly yours,

Conservation Division Agent