



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

APR 1 1963
 04-01-1963
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Ray Richardson of Southwest Casing Pulling Chas this date requested permission to plug the following described well:

D. G. Hanson
 Mr. Richardson guarantees payment of the plugging fee.

Operator's full Name: D. G. Hanson,

Complete Address: Box # 195, Logan, Kansas.

Lease Name: Gackstatter Well No. 1

Location: NE-NE-SE Sec. 28 Twp. 5 Rge. (E) (W) 21

County Norton Total Depth 3690 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Richardson was instructed to plug the well as follows:

232'-8 5/8" surface casing, cement circulated w/100 Sx.

3685'-5 1/2" casing cemented w/150 Sx.

Sand well back to 3675' and set 5 Sx cement w/dump bailer.

Pull 5 1/2" to 550', circulate heavy gel mud and displace 20 Sx

cement. Pull 5 1/2" to 220' and displace 20 Sx cement thru 5 1/2".

Pull 5 1/2", set bridge @ 35' and 10 Sx cement to bottom of cellar.

Very truly yours,

H. L. Nichols
 Conservation Division Agent