


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-137-00642-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Norton County. Sec. 26 Twp. 5 Rge. (E) 21 (W)
Location as "NE/CNW%SW%" or footage from lines SW SE SE
Lease Owner Cities Service Oil Co.
Lease Name Dedrick Well No. 1
Office Address Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 12/9 19 57
Application for plugging filed 12/10 19 57
Application for plugging approved 12/16 19 57
Plugging commenced 12/9 19 57
Plugging completed 12/10 19 57
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3730 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	240'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole w/heavy mud thru drill pipe, set wooden plug at 600' with 1/2" sx hulls and 20 sx cement. Fill hole w/heavy mud thru drill pipe to 220', set wooden plug w/1/2" sx hulls and 20 sx cement. Fill hole w/heavy mud to 40', set wooden plug with 1/2" sx hulls, fill hole to surface with 10 sx. cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Lohmann & Johnson 12-23-57
Address Evansville, Indiana

STATE OF KANSAS, COUNTY OF BARTON, ss.
M. M. Hardin (employee of owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M M Hardin

Box 553, Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of December, 19 57

My commission expires March 12, 1959

V. D. Smith
Notary Public.

PLUGGING
FILE SEC 26 T 5 R 21W
BOOK PAGE 69 LINE 15

WELL RECORD

15-137-00642-00-00

WILDCAT.....

DISCOVERY.....

POOL.....

COMPANY Cities Service Oil Co. WELL # 1 FARM Bedrick

LOCATION 370' E and 770' W of NE corner Section 26, Township 5, Range 22E

ELEV. 2264 (2262 Cr). CO. Horton STATE Kansas

IP. Dry Hole P & A 12-9-57

PERFS.....

FRAC..... ACID None

T.D. 3730' PBTD..... GRAV/GOR.....

DRLG. COMM. 11-28-57 COMP. 12-8-57 CONTRACTOR Johnson

CASING RECORD:

8 5/8" @ 240' with 200 sacks cement

Formation Record:

sand & shale	0 - 240
shale, sand & shells	1000
shale	1045
anhyprite	1082
shale	2240
lime & shale	2440
lime	2694
cored lime (rec. 4')	2696
cored lime, shale & sand (rec. 22")	2701
cored sand (no rec.)	2702
sand	2718
granite wash	2730

Topsoil	2641
Hecker	2645
Dodge	2651
Lanning	2666
Base Kansas City	2692
Reagan	2700
Granite Wash	2718
Fertilization	12'
T. S.	2730

BIT 2696 - 2702, open 1 hr, rec. 20' heavily oil-cut mud, 62' thin oily mud & 93' sandy salt water; SHP 10318/30 minutes.

Show Tests (Surfs)

900' - 1"
1000' - 1"
1500' - 1"
2000' - 1"
2500' - 1"
3000' - 1"
3500' - 0"

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1957

CONSERVATION DIVISION
Wichita, Kansas

12-23-57

7 7/8" Rotary Hole

PLUGGING
 FILE SEC 26T 5 R.21W
 BOOK PAGE 69 LINE 15