

STATE OF KANSAS
STATE CORPORATION COMMISSION
Wichita State Office Building
130 South Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-177

15-137-00540-60-00
API NUMBER drilled 1960

LEASE NAME Kemper

WELL NUMBER 3

4950 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 26 TWP. 5S RGE. 21W (E) or (W)

COUNTY Norton

Date Well Completed 9-9-60

Plugging Commenced 3-14-02

Plugging Completed 3-14-02

LEASE OPERATOR R.P. Nixon Operations, Inc.

ADDRESS 207 West 12th Street Hays, KS 67601

PHONE #(785) 628-3834 OPERATORS LICENSE NO. RECEIVED
ST. CORPORATION COMMISSION

Character of Well oil

(Oil, Gas, D&A, SWD. Input, Water Supply Well)

APR 02 2002

Conservation Division
Wichita, Kansas

The plugging proposal was approved on 9-18-01 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 Filed? unknown If not, is well log attached? yes

Producing Formation Arbuckle Depth to Top 3602' Bottom 3622' T.D. 3622'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	155'	None
				5 1/2"	3604'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Perf'd casing @ 1775' w/2 shots and 1100' w/2 shots. Tied on to casing and pumped 240 sx 60/40 Pozmix cement, 10% gel with 4 sacks of hulls. Max. pressure was 600# psi, shut-in pressure was 350# psi. Tied on to casing annulus and pumped 50 sx 60/40 Pozmix, w/1 sack of hulls @ 100# psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. 99996
Address Box 31 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.


Dan A. Nixon (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 207 West 12th St. Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 29th day of March, 2002

[Signature]
Notary Public



Commission Expires: 3/25/2005

OR

ALLIED CEMENTING CO., INC.

10266

Federal Tax I.D.# [REDACTED]

SHIP TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

R

DATE <u>3/14/02</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>7:45 A.M.</u>	JOB START	JOB FINISH <u>8:50 A.M.</u>
LEASE <u>Kemper</u>	WELL# <u>3</u>	LOCATION <u>Logan Oxy Camp 3W 34N</u>			COUNTY <u>Norton</u>	STATE <u>Ks</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)				<u>W Juto</u>			

CONTRACTOR _____ OWNER _____
TYPE OF JOB OAD
HOLE SIZE _____ T.D. _____
CASING SIZE 5 1/2 DEPTH _____
TUBING SIZE _____ DEPTH _____
DRILL PIPE _____ DEPTH _____
TOOL _____ DEPTH _____
PRES. MAX _____ MINIMUM _____
MEAS. LINE _____ SHOE JOINT _____
CEMENT LEFT IN CSG. _____
PERFS. _____
DISPLACEMENT _____

EQUIPMENT
PUMP TRUCK CEMENTER Paul
177 HELPER Jason
BULK TRUCK
362 DRIVER Brent
BULK TRUCK
213 DRIVER Darin

CEMENT
AMOUNT ORDERED 325 60/40 100% Gel
5 Halls
USED 2405x
COMMON 174 @ 665 1157 40
POZMIX 116 @ 355 411 40
GEL 21 @ 10 00 210 00
CHLORIDE _____ @ _____
Halls 5 @ 18 00 90 00
_____ @ _____
_____ @ _____
_____ @ _____
HANDLING 353 @ 10 353 00
MILEAGE 44/SK / Mile 988 40
70
TOTAL 3245 60

REMARKS:

Annulus 505x 1 Hall 100psi.
5 1/2 Csg - 2405x 4 Halls 600 psi. Max
Shut in to 350 psi.

SERVICE

DEPTH OF JOB _____
PUMP TRUCK CHARGE _____ 475 00
EXTRA FOOTAGE _____ @ _____
MILEAGE _____ @ _____
PLUG _____ @ _____
_____ @ _____
_____ @ _____
TOTAL 475 00

CHARGE TO: R.D. Nixon
STREET _____
CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____ @ _____
_____ @ _____
_____ @ _____
_____ @ _____
_____ @ _____
TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
TOTAL CHARGE _____
DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE _____


PRINTED NAME _____

D G HANSEN #3 KEMPER 26-5-21W
 NE NW NE
 Contr. C-G DRILLING NORTON County
 E 2190 RB Comm. Comp. 9-9-60 IP 32 BOPD

Tops	Depth	Datum
ANH	1778	+412
HEEB	3329	-1139
TOR	3356	-1166
KC	3372	-1182
B/KC	3560	-1370
ARB	3602	-1412
TD	3622	-1432

Casing
 8" 155
 5" 3604

 ACID 1500

RAY WEST POOL


INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

RECEIVED
 APR 02 2002
 KCC WICHITA