

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-137-00558-00-00

API NUMBER drilled 6/60

LEASE NAME Kemper

WELL NUMBER 1

4950 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 26 TWP. 5 RGE. 21 (E) or (W)

COUNTY Norton

Date Well Completed 6/10/60

Plugging Commenced 9:00 A.M. 2/18/88

Plugging Completed 11:45 A.M. 2/18/88

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE# (913) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 18, 1988 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3638 Bottom 3647 T.D. 3647

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	158.24'	None
				5 1/2"	3639'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Down 5 1/2" csg., at 1000# max. pressure, mixed 2 sx hulls, then mixed 2 sx hulls with 150 sx cement, and shut in at 600#.

Down annulus (8 5/8" csg.) at 400# max. pressure, mixed 1 sx hulls with 50 sx. cement, and shut in at 200#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. \_\_\_\_\_

Address Box 31, Russell, Kansas 67665

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Harold Parsons (Employee of Operator) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Harold Parsons

(Address) Box 353, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 29 day of February, 19 88



Betty Jane Bittel  
Notary Public Betty Jane Bittel

My Commission Expires: July 17, 1988.

3458

W E L L L O G

OPERATOR	D. G. Hansen	SEC.	26-5-21W
WELL NAME	Kemper #1	LOC.	NW NW NE
TOTAL DEPTH	3642'	COUNTY	Norton
COMM.	June 3, 1960	DATE	June 10, 1960
RIG NO.	1	STATE	Kansas
		ELEVATION	2225' R.B.
CASING: Ran 158.24' (8 jts.) 8-5/8" OD Surface Casing.		PRODUCTION: Producing	
Set 5-1/2" OD Casing @3639' (116 jts.)			

All measurements taken from the top of rotary casing.

FROM	TO	FORMATION	VERTICAL	REMARKS
0	860	Shale-Sand		
860	1235	Sand-Shale-Sand		
1235	1660	Shell-Shale-Red Bed		
1660	1810	Red Bed-Shale		
1810	1854	Anhydrite		
1854	1970	Shale		
1970	2100	Shale-Shell	0° - 2500	
2100	2820	Shale-Lime	0° - 2750	
2820	3260	Lime-Shale	0° - 3000	
3260	3330	Shale-Lime	0° - 3250	
3330	3480	Lime-Shale		
3480	3580	Lime	0° - 3500	
3580	3637	Lime-Shale		
3637	3642	Lime		

STATE OF KANSAS )  
 COUNTY OF SEDGWICK ) SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C. G. DEWOLFE CO.

By

*G. F. Galloway*  
 G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 13th day of June, 1960.

My commission expires:  
 May 20, 1961

Notary Public

Notary Seal  
 Notary Public  
 State of Kansas  
 My Commission Expires May 20, 1961