

15-137-00546-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER \_\_\_\_\_  
LEASE NAME Fee  
WELL NUMBER E-3  
SPOT LOCATION NE NW SW  
SEC. 26 TWP. 5S RGE. 21W (E) or ( )  
COUNTY Norton  
Date Well Completed \_\_\_\_\_  
Plugging Commenced 4-2-86  
Plugging Completed 4-4-86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Dane G. Hanson Trust  
ADDRESS Box 187 Logan, Kansas 67646  
PHONE # 913,689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes  
Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3682'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	198.69'	None
				5-1/2"	3678'	1027'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3630' and 5 sacks cement. Shot pipe @1427', 1204', 1027' and pulled a total of 32 joints (1027') of 5-1/2" casing. Plugged surface with 3 hulls, 29 gel, 100 cement, 1 hull, 11 gel and 80 cement. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso  
(Address) Box 347 Chase, Kansas 67524

RECEIVED  
STATE CORPORATION COMMISSION  
APR 13 1986  
CONSERVATION DIVISION  
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 9th day of April, 1986

Irene Hoover  
Notary Public

My Commission expires:

