

STATE OF KANSAS
STATE CORPORATION COMMISSION
Wichita State Office Building
130 South Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-177

15-137-00545-00-00
API NUMBER drilled 8-8-59

LEASE NAME Fee E

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1650 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR R.P. Nixon Operations, Inc.

SEC. 26 TWP. 5S RGE. 21W (E) or (W)

ADDRESS 207 West 12th Street Hays, KS 67601

COUNTY Norton

PHONE #(785) 628-3834 OPERATORS LICENSE NO. 5252

Date Well Completed 11-6-59

Character of Well oil

Plugging Commenced 3-14-02

(Oil, Gas, D&A, SWD. Input, Water Supply Well)

Plugging Completed 3-14-02

The plugging proposal was approved on 9-18-01 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 Filed? unknown If not, is well log attached? yes - GRN log

Producing Formation Arbuckle Depth to Top 3665' Bottom 3677'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORDS

Formation	Content	From	To	Size	Put in	Pulled out
				8 7/8"	160'	None
				5 1/2"	3667'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Perf'd casing w/2 shots @ 1850' and 2 shots @ 1175'. Pumped down casing w/325 sx of 60/40 Pozmix, 10% gel and 5 sacks of hulls. Max. pressure was 500 psi and shut-in was 250 psi. Tied on to 5 1/2" casing annulus and pressured to 700 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. 99996
Address Box 31 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations, Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Dan A. Nixon (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 207 West 12th St. Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 29th day of March, 2002



[Signature]
Notary Public

OR

D G HANSEN

#1 FEE 'E'

26-5-21W
SW NW SW

Contr. C-G DRLG

NORTON County

E 2255RB Comm. 8-8-59 Comp. 11-6-59 IP

25 BOPD

Tops	Depth	Datum
ANH	1835	+420
TOP	3228	-973
HEEB	3394	-1139
TOR	3419	-1164
LANS	3437	-1182
B/KC	3623	-1368
ARB	3665	-1410
TD	3677	-1422

Casing

8" 160

5" 3667

CO 3677: ACID 500

RAY WEST POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

RECEIVED
APR 02 2002
KCC WICHITA