

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Wichita State Office Building  
130 South Market, Room 2078  
Wichita, Kansas 67202  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD  
K.A.R.-82-3-177

15-137-01001-0000  
API NUMBER completed 7-25-58

LEASE NAME Wiltrout

WELL NUMBER 7

4290 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 27 TWP. 5S RGE. 21W (E) or (W)

COUNTY Norton

Date Well Completed 7-25-58

Plugging Commenced 6-5-00

Plugging Completed 6-5-00

**AUG 14 2000**

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

CONSERVATION DIVISION  
Wichita, Kansas

LEASE OPERATOR R.P. Nixon Operations, Inc.

ADDRESS 207 West 12th Street Hays, KS 67601

PHONE #(785) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well oil

(Oil, Gas, D&A, SWD. Input, Water Supply Well)

The plugging proposal was approved on 5/24/00 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 Filed? ? bought from If not, is well log attached? \_\_\_\_\_  
R.L. Hrbeck - Lic. #31274

Producing Formation Arbuckle Depth to Top 3585' Bottom 3588' T.D. 3588'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	217'	None
				5 1/2"	3585'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Ran tubing to 1886'. Pumped 100 sx 60/40 Pozmix, 10% gel cement, with 200# hulls. Pulled tubing to 948' and pumped 100 sx same cement circulated cement. Came out w/tubing. Topped off casing with 25 additional sacks of cement. Tied onto 5 1/2" annulus and pumped 45 sx cement, max. pressure was 300#. Carl Goodrow approved the job.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor R.P. Nixon Operations, Inc. License No. 5252  
Address 207 West 12th Street Hays, KS 67601-3898

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Dan A. Nixon (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) 207 West 12th St. Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 14th day of August, 2000

[Signature]  
Notary Public

My Commission Expires: 3/12/2001



Form CP-4  
Revised 05-88