

STATE OF KANSAS
STATE CORPORATION COMMISSION
Wichita State Office Building
130 South Market, Room 2078
Wichita, Kansas 67202
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD
K.A.R.-82-3-177

15-137-00717-0000
API NUMBER completed 10-25-57

AUG 14 2000

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Wiltrout

WELL NUMBER C-2

1650 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 27 TWP. 5S RGE. 21W (E) (W)

COUNTY Norton

Date Well Completed 10-25-57

Plugging Commenced 6-1-00

Plugging Completed 6-1-00

CONSERVATION DIVISION
Wichita, Kansas

LEASE OPERATOR R.P. Nixon Operations, Inc.

ADDRESS 207 West 12th Street Hays, KS 67601

PHONE #(785) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well oil

(Oil, Gas, D&A, SWD. Input, Water Supply Well)

The plugging proposal was approved on 5/24/00 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 Filed? ? bought from If not, is well log attached? _____

R.L. Hrbeck - Lic. #31274

Producing Formation Reagan Sand Depth to Top 3627' Bottom 3630' T.D. 3630'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	226'	None
				5 1/2"	3629'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Ran tubing to 1886'. Pumped 100 sx 60/40 Pozmix, 10% gel cement, with 250# hulls. Pulled tubing to 948' and pumped 75 sx same cement circulated cement. Came out w/tubing. Tied onto 5 1/2" annulus and pumped 50 sx cement. Topped off casing with 5 additional sacks of cement. Carl Goodrow approved the job.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor R.P. Nixon Operations, Inc. License No. 5252

Address 207 West 12th Street Hays, KS 67601-3898

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Dan A. Nixon (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) 207 West 12th St. Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 11th day of August, 2000

[Signature]
Notary Public

My Commission Expires: 3/12/2001



Form CP-4
Revised 05-88