


15-137-00715-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Norton County, Sec. 27 Twp. 5S Rge. (E) 21W(W)
Location as "NE/CNW%SW%" or footage from lines NE SW NE
Lease Owner Varn Petroleum Company
Lease Name Wiltroat Well No. 3
Office Address 502 Central Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 6-19-57 19
Application for plugging filed 6-25-65 19
Application for plugging approved 6-28-65 19
Plugging commenced 6-30-65 19
Plugging completed 7-3-65 19
Reason for abandonment of well or producing formation 100% water

If a producing well is abandoned, date of last production June 1961
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation Arbuckle Depth to top 3629 Bottom Total Depth of Well 3631 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Toronto	Oil show	3380	3390	8-5/8	230	00
Lansing, K.G.	Oil show	3397	3580	5 1/2	3630	1714
Arbuckle	oil	3629	3631			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Shot casing 1700'. Pulled casing to 555' from top. Pumped 20 sacks gel mud thru 5 1/2" casing. Pumped 20 sacks cement thru 5 1/2" casing @555'. Pulled 5 1/2" casing to 200'. Pumped 20 sacks thru 5 1/2" casing. Finished pulling casing. Removed tools from over hole. Bailed mud down in surface pipe to 35'. Made rock bridge from 35' to 30'. 10 sacks cement from 30' to base.

RECEIVED
STATE CORPORATION COMMISSION

JUL 12 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Santa-Fe Pipe & Supply, Inc. 17-12-65
Address P. O. Box 562, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Otis E. Anderson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Otis E. Anderson

Varn Petroleum Co., 502 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of July, 19 65

Joan White Notary Public.

My commission expires 6-25-68



15-137-00715-00-00

VARN PETROLEUM COMPANY
WILTROUT #3
Well Log

NE-SW-NE Sec. 27-5S-21E
Norton County, Kansas

Surface, sand & clay	0-231
Shale & shells	231-800
Shale w/strks. sand	800-1100
Sand	1100-1350
Sand & shale	1350-2020
Lime & shale	2020-3095
Sandy lime & shale	3095-3160
Shale	3160-3235
Lime & shale	3235-3300
Lime	3300-3625
Arbuckle Lime	3625-3631 TD

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1965

7-1-65
CONSERVATION DIVISION
Wichita, Kansas