

15-137-00712-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTON County. Sec. 27 Twp. 5S Rge. 121 (W)

Location as "NE/CNW%SW%" or footage from lines SE SE NW
Lease Owner VARN PETROLEUM COMPANY
Lease Name KENDRICK Well No. 1
Office Address 502 CENTRAL BUILDING, WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed NOVEMBER 23 1957
Application for plugging filed MARCH 18 1966
Application for plugging approved 19
Plugging commenced MARCH 21 1966
Plugging completed MARCH 26 1966
Reason for abandonment of well or producing formation DEPLETED

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. NICHOLS
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3603 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	222'	none
				5 1/2"	3600'	2188.21'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3603' - 3585' - SAND
3585' - 3545' - 5 SACKS CEMENT
3545' - 540' - MUD
540' - 474' - PUMPED 18 SACKS JEL MUD
474' - 150' - PUMPED 40 SACKS CEMENT
150' - 35' - MUD
35' - 30' - ROCK BRIDGE
30' - BASE - PUMPED 10 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION

APR 11 1966

CONSERVATION DIVISION
Wichita, Kansas

4-11-66

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.
Address P. O. BOX 562, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
T. L. NUTT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt
P. O. BOX 562, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 6TH day of APRIL, 1966.

Mary M. Guenier
Notary Public.

My commission expires JULY 31, 1966

15-137-00712-00-00

COPY


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- JOCEYLN-VARN OIL CO.
Farm- Kendrick No. 1

SEC. 27 T. 5 R. 21W
SE SE NW

Total Depth. 3603'
Comm. 9-8-57 Comp. 9-23-57
Shot or Treated.
Contractor. Trusco Drlg.
Issued. 5-23-59

County Norton
KANSAS



Elevation. 2177' DF

Production. 648 BOPD

Figures Indicate Bottom of Formations.

soil, sand	65
shale, sand	223
shale	235
shale	1000
sand	1185
sand, shale	1279
sand, shale	1530
red bed, shale	1760
Anhydrite	1800
red bed, shale	1875
red rock,	1940
shale, shells	1995
shale, shells	2185
lime, shale	2375
lime, shale	2455
shale, lime	2570
lime, shale	2720
lime, shale	2800
lime, shale	2843
lime, shale	2945
lime, shale	3247
lime	3451
lime	3603
Total Depth	

TOPS: SCOUT	
Heebner	3322
Toronto	3348
Lansing	3366
Reagan Sand	3599

RECEIVED
STATE CORPORATION COMMISSION

APR 11 1966

CONSERVATION DIVISION
Wichita, Kansas