

STATE OF KANSAS
STATE CORPORATION COMMISSION
200, Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-137-00551-00-00

API NUMBER Reached T.D. 11/18/58

LEASE NAME Watkins

WELL NUMBER 3

330 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 27 TWP. 5s RGE. 21w (X) or (W)

COUNTY Norton

Date Well Completed 12/3/58

Plugging Commenced 1:15 P.M. 4/11/89

Plugging Completed 2:15 P.M. 4/11/89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE #013) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on April 11, 1989 (date)

by Dale F. Balthazor (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3638 Bottom 3650 T.D. 3650

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	177'	None
				5 1/2"	3639'	None

Describe in detail the manner in which the well was plugged, indicating where the fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pumped down 8 5/8" pres. to 600# holding pumped down 5 1/2" casing
300 sks cement w/500# Hulls. 700# maz holding 300#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No.

Address P. O. Box 31, Russell, Kansas 67665

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Dane G. Bales, Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature)

Dane G. Bales

(Address) P. O. Box 187, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 20th day of April, 1989

My Commission Expires: July 17, 1992

Notary Public

Betty Jane Bittel



BETTY JANE BITTEL
State of Kansas
My Appt. Exp. July 17, 1992

Form CP-4
Revised 07-87

15-137-00551-00-00

CONTRACTOR'S WELL LOG

OPERATOR D. G. Hansen WELL NAME Watkins #3
LOCATION SW SE SE SEC. 27-5-21W RIG NO. 1
COUNTY Norton STATE Kansas
COMMENCEMENT DATE November 9, 1958 COMPLETION DATE November 18, 1958

LOG OF WELL

Elevation 2223' kelly bushing.
All measurements taken from the top of kelly bushing.

FROM	TO	FORMATION	DEVIATION	REMARKS:
			FROM VERTICAL	
0	100	Surface Soil-Sand		
100	177	Sand-Shale		
177	285	Sand-Shale		
285	995	Shale		
995	1080	Sand		
1080	1175	Shale-Sand		
1175	1240	Sand		
1240	1400	Shale-Sand		
1400	1425	Shale		
1425	1730	Shale		
1730	1805	Red Bed		
1805	1838	Anhydrite		
1838	1905	Shell-Shale		
1905	2235	Shale-Shell		
2235	2385	Shale-Lime		
2385	2615	Lime-Shale	0° - 2500	
2615	2785	Shale-Lime	0° - 2750	
2785	2890	Lime-Shale		
2890	3010	Lime-Shale	0° - 3000	
3010	3100	Lime-Shale		
3100	3174	Lime-Shale		
3174	3255	Lime-Shale	0° - 3250	
3255	3330	Lime-Shale		
3330	3340	Lime-Shale		DST 3327-3340'
3340	3405	Lime-Shale		
3405	3440	Lime		
3440	3469	Lime		
3469	3510	Lime-Shale		
3510	3565	Lime		
3565	3630	Lime		
3630	3643	Lime-Shale		

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1989
CONSERVATION DIVISION
Wichita, Kansas

CASING LEFT IN HOLE AFTER COMPLETION

Ran 177.85' (9 jts.) 8-5/8" OD Surface Casing.
Set 5-1/2" OD Casing @3639' (115 jts.)

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway
G. F. Galloway

SUBSCRIBED AND SWORN TO BEFORE ME THIS 21st day of November, 1958.

Vicky Jacobs, Notary Public

My commission expires: May 20, 1959