

STATE OF KANSAS
STATE CORPORATION COMMISSION
Wichita State Office Building
130 South Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-177

15-137-00549-00-00
API NUMBER drilled 6-13-58

RECEIVED

SEP 28 2001

9-28-2001

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Watkins

WELL NUMBER 1

990 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 27 TWP. 5S RGE. 21W (E) or (W)

COUNTY Norton

Date Well Completed 6-13-58

Plugging Commenced 9-26-01

Plugging Completed 9-26-01

LEASE OPERATOR R.P. Nixon Operations, Inc.

ADDRESS 207 West 12th Street Hays, KS 67601

PHONE #(785) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well oil

(Oil, Gas, D&A, SWD. Input, Water Supply Well)

The plugging proposal was approved on August 7, 2001 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 Filed? unknown If not, is well log attached? yes

Producing Formation Arbuckle Depth to Top 3631' Bottom 3635' T.D. 3625'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 7/8"	177'	None
				5 1/2"	3631'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Tied on to 5 1/2" annulus and pressured up and held 500#. Tied on to casing and pumped 320 sacks of 60/40 Pozmix, 10% gel with 300# hulls. Maximum pressure was 1000#, shut-in pressure 500#. District 4 KCC man Jay Pfiefer witnessed the job.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor R.P. Nixon Operations, Inc. License No. 5252
Address 207 West 12th Street Hays, KS 67601-3898


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Dan A. Nixon (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 207 West 12th St. Hays, KS 67601



SUBSCRIBED AND SWORN TO before me this 27th day of September, 2001

[Signature]
Notary Public

My Commission Expires: 3/12/2005

OK

15-137-00549-00-00

CONTRACTOR'S WELL LOG

OPERATOR D. G. Hansen WELL NAME Watkins #1
LOCATION NE SW SE SEC. 27-5-21W RIG NO. 1
COUNTY Norton STATE Kansas
COMMENCEMENT DATE October 30, 1957 COMPLETION DATE November 6, 1957

LOG OF WELL

Elevation 2218' rotary bushing.
All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0	177	Shale		
177	765	Sand-Shale		
765	985	Sand-Shale		
985	1240	Sand		
1240	1545	Sand-Shale		
1545	1800	Red Bed		
1800	1830	Anhydrite		
1830	1838	Anhydrite		
1838	2330	Shale-Shell		
2330	2545	Lime-Shale	0° - 2500	
2545	2770	Lime-Shale	0° - 2750	
2770	2910	Lime-Shale		
2910	3015	Lime-Shale	0° - 3000	
3015	3190	Lime-Shale		
3190	3285	Lime-Shale	0° - 3250	
3285	3355	Lime-Shale		
3355	3411	Lime-Shale		
3411	3461	Lime-Shale		
3461	3499	Lime-Shale		
3499	3523	Lime-Shale		
3523	3575	Lime-Shale		
3575	3635	Lime-Shale		

RECEIVED

SEP 28 2001

KCC WICHITA

DST 3498-3523'

CASING LEFT IN HOLE AFTER COMPLETION

Ran 177.31' (9 jts.) 8-5/8" OD Surface casing.
Set 3641.96' (114 jts.) 5-1/2" Casing.

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway
G. F. Galloway

SUBSCRIBED AND SWORN TO BEFORE ME THIS 14th day of November, 1957.

Vicky Jacobs
Vicky Jacobs, Notary Public

My commission expires: May 20, 1959

ALLIED CEMENTING CO., INC. 09883

Federal Tax I.D.#

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

R

DATE 9-26-01	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION	JOB START	JOB FINISH
LEASE Walker	WELL # 1	LOCATION Hogan 35 50	COUNTY Phillips	STATE IL			
OLD OR NEW (Circle one)							

CONTRACTOR		OWNER	
TYPE OF JOB No			
HOLE SIZE	T.D.	CEMENT	
CASING SIZE 5'2	DEPTH	AMOUNT ORDERED 3.50 60/40 100 gals	
TUBING SIZE	DEPTH	300 # hulls	
DRILL PIPE	DEPTH	used 320	
TOOL	DEPTH		
PRES. MAX	MINIMUM	COMMON @	
MEAS. LINE	SHOE JOINT	POZMIX @	
CEMENT LEFT IN CSG.		GEL @	
PERFS.		CHLORIDE @	
DISPLACEMENT		@	
EQUIPMENT		@	
PUMP TRUCK	CEMENTER	@	
# 3-15	HELPER	@	
BULK TRUCK		@	
# 254	DRIVER	HANDLING @	
BULK TRUCK		MILEAGE @	
#	DRIVER		

RECEIVED

SEP 28 2001

TOTAL

REMARKS:

KCC WIGHT SERVICE

Press 8 5/8 to 500#s held.
mixed 320 @ 40 w/ 300# hulls
down 5h
W.A. & M. 1000#
Shut in 500#

DEPTH OF JOB	
PUMP TRUCK CHARGE	
EXTRA FOOTAGE	@
MILEAGE	@
PLUG	@
	@
	@

CHARGE TO: R.P. Walker
STREET
CITY STATE ZIP

FLOAT EQUIPMENT

@	
@	
@	
@	
@	

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment
and furnish cementer and helper to assist owner or
contractor to do work as is listed. The above work was
done to satisfaction and supervision of owner agent or
contractor. I have read & understand the "TERMS AND
CONDITIONS" listed on the reverse side.

TOTAL	
TAX	
TOTAL CHARGE	
DISCOUNT	
IF PAID IN 30 DAYS	

SIGNATURE

R.P. Walker

PRINTED NAME