

State of Kansas



FORM CP-2

15-147-20358-00-00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Larry Hicks of Kandrilco LTD. has this

date requested permission to plug the following described well:

Operator's Full Name: K.R.M. Petroleum Corporation

Complete Address: 817 17th St., Suite #820, Denver, Colo. 80202

Lease Name: Patton Well No. #1-9

Location: SW NE Sec. 9- Twp. 5 N Rge. 17 E (E) (W)

County: Phillips Total Depth: 3562'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Larry Hicks was instructed to plug the well as follows:

8 5/8"-202' s.p. cuc. w/150 sacks common-2% Gel.-3% Cal. Cl. RECEIVED  
STATE CORPORATION COMMISSION  
Ordered 135 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs. DEC 14 1981

1st plug @ 720' w/70 sacks cement  
2nd plug @ 210' w/40 sacks cement  
3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

CONSERVATION DIVISION  
Wichita, Kansas

Circulated with 10 sacks of cement in rat hole, and 5 sacks in mouse hole.

Very truly yours,

Conservation Division Agent