



15-137-00559-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 5 1974
CONSERVATION DIVISION
Wichita, Kansas
2-5-74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. John Parsons of D. G. Hansen Trust has this

date requested permission to plug the following described well:

Mr. Parsons guarantees payment of the plugging fee.

Operator's full Name: D. G. Hansen Trust,

Complete Address: Box #187, Logan, Kansas.

Lease Name: Kemper Well No. 2

Location: App: SW-NW-NE Sec. 26 Twp. 5 Rge. (E)(W) 21

County: Norton Total Depth 3642 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Parsons was instructed to plug the well as follows:

167'--8 5/8" Surface casing, cement circulated with 130 Sx.
3625'--5 1/2" Production casing cemented on bottom with 125 Sx. Open hole
completion, no plug-back nor perforations indicated.

Sand well back to 3600' and set 5 Sx. cement with dump bailer. Pull 5 1/2"
casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft.
cement, staged.

Very truly yours,

N. L. Fickels
Conservation Division Agent