

State of Kansas



FORM - CP-2
Rev. 9-8-64

15-137-00715-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
MORT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 7 1965
7-7-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Owen Bailey of Santa Fe Pipe & Supply has this date requested permission to plug the following described well:

Varn Petroleum Co.
Mr. Bailey guarantees payment of the plugging fee.

Operator's full Name: Varn Petroleum Company,

Complete Address: 310 Sutton Place, Wichita, Kansas.

Lease Name: Wiltroat Well No. 3

Location: NE-SW-NE Sec. 27 Twp. 5 Rgs. (E) (W) 21

County Norton Total Depth 3631 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bailey was instructed to plug the well as follows:

230' -- 3 5/8" Surface pipe, cement circulated.
3630' -- 5 1/2" Production casing. No perforations or plug back.

Sand well back to 3615 and set 5 Sx. cement with dump bailer.
Pull 5 1/2" to 600' and circulate heavy gel mud. Pull 5 1/2" to 540' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 210' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2", set bridge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. D. Nichols
Conservation Division Agent