



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 APR 5 1966
 4-5-66
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Owen Bailey of Santa Fe Pipe & Supply has this

date requested permission to plug the following described well:

Varn Petroleum Co.

Mr. Bailey guarantees payment of the plugging fee.

Operator's full Name: Varn Petroleum Company,

Complete Address: 502 Central Building, Wichita, Kansas.

Lease Name: Kendrick Well No. 2

Location: NE-NE-14W Sec. 27 Twp. 5 Rge. (E) (W) 21

County Norton Total Depth 3639 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bailey was instructed to plug the well as follows:

214' -- 8 5/8" Surface pipe, cement circulated with 160 Sx.
3637 1/2' -- 5 1/2" Production casing cemented with 100 Sx. No plug
back. No perforations.

Sand well back to 3625' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" to 550' and circulate heavy gel mud. Pull 5 1/2" to
490' and displace 20' Sx. cement thru 5 1/2". Pull 5 1/2" to 210'
and displace 20' Sx. cement thru 5 1/2". Pull 5 1/2", set rock bridge
@ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
 Conservation Division Agent