



15-137-00712-00-00

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 5 1966  
4-5-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Owen Bailey of Santa Fe Pipe & Supply has this

date requested permission to plug the following described well:

Varn Petroleum Company

Mr. Bailey guarantees payment of the plugging fee.

Operator's full Name: Varn Petroleum Company,

Complete Address: 502 Central Building, Wichita, Kansas.

Lease Name: Kendrick Well No. 1

Location: SE-SE-NW Sec. 27 Twp. 5 Rge. (E) (W) 21

County Norton Total Depth 3603 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Bailey was instructed to plug the well as follows:

222' -- 8 5/8" Surface pipe, cement circulated with 175 Sx.  
3600' 5 1/2" Production casing cemented with 100 Sx. No plug back  
no perforations.

Sand well back to 3585 and set 5 Sx. cement with dump bailer.  
Pull 5 1/2" to 550' and circulate heavy gel mud, Pull 5 1/2" to  
490' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 210' and  
displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" set rock bridge @  
35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

A. L. Nichols  
Conservation Division Agent