



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

AUG 19 1963  
 8-19-63  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Merle Herring of Barnes Pipe Pulling Co. has this

date requested permission to plug the following described well:  
Fender Pipe & Supply, Inc.,

Mr. Herring guarantees payment of the plugging fee.

Operator's full Name: Fender Pipe & Supply, Inc.,

Complete Address: Box #202, Russell, Kansas.

Lease Name: Bullock Well No. 1

Location: NW-NE-NW Sec. 13 Twp. 5 Rge. (E) (W) 22

County Norton Total Depth 3560' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Herring was instructed to plug the well as follows:

195'--8 5/8" Surface pipe, cement circulated.  
3558'--5 1/2" cemented with 125 Sks. Top of perforations @ 3318'.  
Sand well back to 3305' and set 5 Sx cement with Dump Bailer.  
pull 5 1/2" to 550', circulate heavy gel mud and displace 20 Sx cement  
thru 5 1/2". Pull casing to 180' and displace 20 Sx cement thru 5 1/2".  
Pull 5 1/2", set bridge and 10 Sx cement to bottom of cellar.

Very truly yours,

N. L. Nichols  
 Conservation Division Agent