



15-137-20031-00-01

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 3 1971
CONSERVATION DIVISION
Wichita, Kansas
11-3-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Walter Voth of Knight Casing Pulling Co., has this
date requested permission to plug the following described well:

Mr. Voth guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: Voss Well No. 1

Location: SW-NE-SE Sec. 9 Twp. 5 Rge. (E)(W) 22

County: Norton Total Depth 3566' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Voth was instructed to plug the well as follows:

263'--8 5/8" Surface casing, cement circulated.

3563'--5 3/4" Production casing cemented on bottom with 175 Sx. No plug
back nor perforations indicated.

Sand well back to 3550' and set 5 Sx. cement with dump bailer. Pull 5 1/2"
casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Sx.
cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent