



15-137-20037-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 25 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
6-25-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Lowell Moore of C & G Drilling Company has this

date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: Four-Way Operating, Incorporated,

Complete Address: Box #698, Great Bend, Kansas.

Lease Name: Stenger Well No. 1

Location: NE-SE-SE Sec. 11 Twp. 5 Rge. (E)(W) 22

County: Norton Total Depth 3591' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Moore was instructed to plug the well as follows:

211'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 725'.

Circulate hole with heavy mud. Pull DP to 950' and displace 100 Sx.  
cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent