

State of Kansas



15-137-20005-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Don Favinger of Murfin Drilling Company has this  
date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: J. C. Graves--Kern Drilling Company,

Complete Address: 505 Union Center, Wichita, Kansas.

Lease Name: Schulte Well No. 1

Location: SE-SW-NW Sec. 10 Twp. 5 Rge. (E)(W) 22

County Norton Total Depth 3622 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Favinger was instructed to plug the well as follows:

229'--8 5/8" Surface pipe, cement circulated with 175 Sx.  
Dakota section from 1265' to 1459'.

Circulate hole with heavy mud, Pull DP to 1488' and displace 100 Sx.

cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.

Pull DP, set bridge @ 40' with 1/2 sk. hulls and 10 Sx. cement to cellar.

Very truly yours,

RECEIVED  
STATE CORPORATION COMMISSION

*A. L. Nichols*

Conservation Division Agent

SEP 12 1967

9-12-67

CONSERVATION DIVISION  
Wichita, Kansas