



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian

WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 31 1974
CONSERVATION DIVISION
Wichita, Kansas
7-31-74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Keith Gallatin of Indigo Drilling Company has this date requested permission to plug the following described well:

Mr. Gallatin guarantees payment of the plugging fee.

Operator's full Name: Thomas K. Travis,

Complete Address: 348 North Roosevelt, Wichita, Kansas.

Lease Name: Jacobs Well No. 1

Location: SW-NW-SE Sec. 9 Twp. 5 Rge. (E)(W) 22

County: Norton Total Depth 3560' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gallatin was instructed to plug the well as follows:

80'--8 5/8" Surface casing, cement circulated with 110 Sx.

Circulate hole with heavy mud. Pull DP to 900' and displace 70 Sx.

cement thru DP. Pull DP to 125' and displace 20 Sx. cement thru DP.

Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to

bottom of cellar.

Very truly yours,

Conservation Division Agent