

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-20096-00-00

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 28 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address 801 Union Center, Wichita, Kansas.

Lease Name Hildebrand Well No. 1

Location CSE-SW-SW Sec. 15 Twp. 5 Rge. (E) (W) 23

County Norton Total Depth 3600'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Above

Address \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 7:00 AM Day 26 Month 1 Year 1974

The above well was plugged as follows:

230'--7 5/8" Surface casing, cement circulated with 140 Sx.  
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 70 Cu. Ft. cement  
thru DP from 975' to 650'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru  
DP from 245' to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 1/30/74  
INV. NO. 8464-W

Signed: H. G. Nichols  
Well Plugging Supervisor