

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-20095-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1974
CONSERVATION DIVISION
Wichita, Kansas
6-10-74

Operator's Full Name F & M Oil Company, Incorporated,

Complete Address 603 Union Center, Wichita, Kansas.

Lease Name Schaben Well No. 3

Location NE-SE-NW Sec. 22 Twp. 5 Rge. (E) (W) 23

County Norton Total Depth 3590'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 9:15 AM Day 5 Month 6 Year 1974

The above well was plugged as follows:

168'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 110 Cu. Ft. cement
thru DP from 975' to 650'. Pulled DP to 185' and displaced 30 Cu. Ft. cement thru
DP from 185' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. S. Nichols
Well Plugging Supervisor JB

DATE 6/11/74

INV. NO. 9280-W