

DISTRICT CONSERVATION AGENT'S REPORT

15-137-00003-00-00

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SW SW SW

SEC. 11 TWP. 5 RGE. 24W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Allen

Operator Peel - Hardman Address Hoisington, Kans

Field ~~Maxton~~ County Norton

Total Depth 3597 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 173' circulated with cement - 5 1/2" at 3597' with  
150 sax cement behind , perforated and squeezed with 450 Sax  
cement - Lane Wells plugs to 3458', top perforations at  
3441' -

Filled with chat to 3425', set 4 sax cement with dump bailer,  
pulled 2945' 5 1/2", filled hole with mud to 173', set rock bridge  
and 15 sax cement, filled with mud to 35', set rock and 10  
sax cement to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 15 1951

8-15-51

[Signature]  
District Conservation Agent

Date 8-9-51

**PLUGGING**  
FILE SEC 11 TWP 5 RGE 24W  
BOOK PAGE 107 LINE 34