

15-137-00615-00-00

CP-3

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

APR 1 1963
64-01-1963
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name D. G. Hansen,

Complete Address: Box #195, Logan, Kansas.

Lease Name Gackstatter Well No. 1

Location NE-NE-SE Sec. 28 Twp. 5 Rge. (E) (W) 21

County Norton Total Depth 3690

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling Co.,

Address: Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 12 Noon Day 26 Month 3 Year 1963

The Above well was plugged as follows:

232' 8 5/8" surface casing cement circulated w/100 Sx.

3685' 5 1/2" casing cemented w/150 Sx.----Pulled 5 1/2" to 550', circulated

heavy gel mud (18 sacks), and displaced 20 Sx cement thru 5 1/2". Pulled

casing to 220' and displaced 20 Sx cement thru 5 1/2". Pulled casing, set

bridge @ 55' and 10 Sx cement to bottom of cellar. (Recovered 1508' 5 1/2")/.

(Cementing and mudding operations by Sun Oil Well Cementing Co.)

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Pichel
Well Plugging Supervisor

3/29/63
6492-W