

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

13-147-00003-00-00

RECEIVED
STATE CORPORATION COMMISSION

AUG 6 1962

CONSERVATION DIVISION
Wichita, Kansas

8-6-62

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Messman & Rinehart

Complete Address: 518 Pet Bldg Wichita, Kansas

Lease Name Steele Est Well No. 1

Location SW SW NE Sec. 34 Twp. 5 Rge. (E) (W) 20

County Phillips Total Depth 3675

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pilling & Globe Cementing Co

Address: Great Bend, Kansas License No. 399

Operation Completed: Hour 1PM Day 1 Month 8 Year 62

The Above well was plugged as follows:

8 5/8" 215' circulated with cement - 4 1/2" 3575' with 75 sax cement PB 35411
 perforated 3530'
 Sand to 3501', set 3 sax cement with dump bailer - pulled 2011' 4 1/2" to 550',
 circulated hole with heavy mud through 4 1/2" at 550' - 24 sax gel - displaced
 20 sax cement through 4 1/2" at 550', heavy mud to 180', displaced 20 sax cement
 through 4 1/2" - heavy mud to 35', set bridge and filled to bottom cellar with
 cement.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/6/62

INV. NO. 5488-W

Signed: [Signature]
 Well Plugging Supervisor