

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-20052-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1970
CONSERVATION DIVISION
Wichita, Kansas
12-10-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Leben Drilling, Incorporated,

Complete Address Box #486, Great Bend, Kansas.

Lease Name Allen Well No. A-1

Location CNW-NE Sec. 2 Twp. 5 Rge. (E) (W)22

County Norton Total Depth 3508'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Forbes Casing Pulling Company, Incorporated,

Address Box # 211, Great Bend, Kansas. License No. 637

Operation Completed: Hour 2:30 PM Day 8 Month 12 Year 1970

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 175 Sx.
3505'--5 1/2" Production casing cemented on bottom with 125 Sx. Pushed plug to 3200'
sanded back to 3175' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (and
squeezed well with initially 5 sacks hulls and 15 sacks gel then 100 Sx. cement from
1025' to 700' then 12 sacks gel from 700' to 225' and followed with 25 Sx. cement from
225' to 150' then 3 sacks gel from 150' to 30' and finally 10 Sx. cement from 30' to
bottom of cellar. Maximum pump-in pressure-600#..Final shut-in pressure-200#.
(Mudding and cementing by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. L. Nichols
Well Plugging Supervisor

DATE 12/10/70
INV. NO. 3038-W