

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-137-20051-00-00

RECEIVED
STATE CORPORATION COMMISSION
APR 13 1970
CONSERVATION DIVISION
Wichita, Kansas
4-13-70

Operator's Full Name Leben et al.
Complete Address 200 West Douglas, Wichita, Kansas.
Lease Name Schaffer Well No. 1
Location CNE-NE Sec. 3 Twp. 5 Rge. (E) (W) 22
County Norton Total Depth 3619
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Leben Drilling, Incorporated.
Address Box #186, Great Bend, Kansas. License No.
Operation Completed: Hour 1:00 AM Day 7 Month 4 Year 1970

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 100 Sx. cement thru
DP from 975' to 650'. Pulled DP to 215' and displaced 25 Sx. cement thru DP. from
215' to 140'. Pulled DP, set bridge @ 40' with $\frac{1}{2}$ sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 4/13/70
INV. NO. 1703-W