

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-00114-00-00
Spot: SW Sec/Twnshp/Rge: 25-26S-40W
2490 feet from S Section Line, 2490 feet from W Section Line
Lease Name: HELTEMES N A Well #: 3-25
County: HAMILTON Total Vertical Depth: 2568 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA.
Address: 5205 N. O'CONNOR BLVD.
IRVING, TX 75039

L1 Size: 5.5 feet: 2418
PROD Size: 7 feet: 2442 WITH 400 SX CMT
SURF Size: 10.75 feet: 460 WITH 250 SX CMT

\$83⁴⁶

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/08/2004 2:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 35 SX CMT. PLUG AT 500' WITH 75 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/09/2004 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 35 SX CMT & 400# HULLS. TAGGED TOP OF PLUG @ 2208'. 1ST PLUG PULL TO 500'. CIRCULATE HOLE WITH MUD. PUMP 75 SX CMT. 2ND PLUG AT 40-0' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
2487	2497		
2449	2464		
2439	2449		

RECEIVED
DEC 20 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 717' OF 7" CASING.

Plugged through: CSG

District: 01



Signed _____

Ken Jehlik
(TECHNICIAN)

INVOICED
DATE 12-20-04
INV NO 2005060955

Form 2/3