

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-031-21180-00-01  
Spot: SESWNW Sec/Twnshp/Rge: 13-23S-16E  
2922 feet from S Section Line, 4396 feet from E Section Line  
Lease Name: MARTZ Well #: 5  
County: COFFEY Total Vertical Depth: 989 feet

Operator License No.: 32710  
Op Name: LAYMON OIL II, LLC

PROD Size: 2.875 feet: 980  
SURF Size: 7 feet: 63

Address: 1998 SQUIRREL RD  
NEOSHO FALLS, KS 66758

*\$ 35<sup>00</sup>*

Well Type: EOR UIC Docket No: E22467.7 Date/Time to Plug: 10/05/2004 8:00 AM

Plug Co. License No.: 32710 Plug Co. Name: LAYMON OIL II, LLC

Proposal Rcvd. from: MIKE LAYMON Company: LAYMON OIL II, LLC Phone: (620) 963-2495

Proposed Plugging Method: THIS WELL CONSISTED OF 2.875" CASING TO 980' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 2.875" CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL  
Date/Time Plugging Completed: 10/05/2004 12:00 PM

WitnessType: PARTIAL  
KCC Agent: CLAYTON TITEL

Actual Plugging Report:

PLASTIC SPOOLED PIPE WAS RAN INTO THE 2.875" PIPE TO TD. CEMENT WAS PUMPED INTO THE PLASTIC PIPE UNTIL CEMENT CIRCULATED FROM THE 2.875" CASING AT SURFACE. THE PLASTIC PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

Top	Bot	Thru	Comments
938	942	CSG	

RECEIVED  
DEC 20 2004  
KCC WICHITA

RECEIVED  
KCC DISTRICT #3

DEC 16 2004 OPT

CHANUTE, KS

Remarks:

Plugged through: TBG

District: 03

Signed

*Clayton P. Titel*  
(TECHNICIAN)

INVOICED

DATE

12-20-04

INV. NO.

2005060954