

11-25

4-032269

15-137-20212-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- -

NW NE /4 SEC. 02, 05, 22 W
4620 feet from S section line
1980 feet from E section line

Operator license# 6568

Lease: Hansen Estate Unit Well # 8-1

Operator: Kaiser Francis Oil Company

County: Norton 114.34

Address: P.O. Box 21468
Tulsa, OK 74121-1468

Well total depth 3518 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 243 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Co Tools License# 6568

Address: P.O. Box 21468 - Tulsa, OK 74121-1468

Company to plug at: Hour: A.M. Day: 25 Month: November Year: 1997

Plugging proposal received from: John Glenn

Company: Kaiser Francis Oil Company Phone: -

Were: Order 210 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1997

CONSERVATION DIVISION
WICHITA, KANSAS

12-10-97

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:00 A.M., Day: 25 Month: November Year: 1997

Actual plugging report: 8 5/8" set at 243' w/180 sxs. 4 1/2" set at 3509' w/150 sxs.
O.H. 3509' - 3520'. Critical area control shots at 675' and 1706'. Squeezed 4 1/2" with 195
sxs with 500# hulls mixed in. Max. P.S.I. 600#. S.I.P. 0#. Squeezed 8 5/8" with 15 sxs
150#. Held.

Remarks: Allied Cement Company - Oakley, Kansas.

Condition of casing(in hole): GOOD BAD Any plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING Elevation: GL

INVOICED

I did [] did not [] observe the plugging.

Carl Goodrow
(agent)

DATE DEC 12 1997

INV. NO. 49670

11-25 JAN 29 1998